Mr. Osama

M/s. AL KARAM TOWEL



KARACHI

SUB: SUPPLY & INSTALLATION OF PANELS WITH MODIFICATION WORK

Dear Sir,

With reference to your query, attached please find the quotation for the subject project

NOTES:

- 1) Components will be as per attached component list.
- 2) Our offer is valid for 05 days, beyond the validity, M/s. R.A Engineering. reserves the right to review / revise the quotation.
- 3) Delivery / transportation will be Ex-Factory Karachi.
- 4) Above Prices are exclusive of Sales Tax.
- 5) Our offer is for only Supply, Installation and Commissioning mentioned in SOP.
- 6) If delivery is not taken within 10 days after notification / intimation of readiness, extra charges will be applicable.
- 7) Our offer is subject to the Force-Majure.
- 8) Our offer is based on Current US Dollar rate if Dollar rate change our Quotation will be revised accordingly.

MODE OF PAYMENT:

70% advance alongwith order. 30% before delivery.

DELIVERY:

Delivery will be decided at the time of placement.

Best Regards.

Wagas Ghauri M HAMZA

(Assistant Manager)

(Electrical Engineer)

0301-8224498



Schedule Of Prices

CLIENT: AL KARAM TOWEL

PROJECT: M/S Supply of PANELS FOR AL KARAM TOWEL								
S.No.	Description	Qty	Rate (Rs)	Amount(Rs)				
1	SUPPLY OF NEW 3200A BREAKER, COPPER MAIN BUS AND LINKS IN EXISTING PANEL	1	2,426,254	2,426,254				
2	4000A ACB TP ABB BUYBACK AFTER CHECKING CONDITION	1	500,000	500,000				
	Total			1,926,254				
2	SUPPLY OF 3200A AUTO PHASE REVERSAL PANEL	1	6,277,575	6,277,575				
3	SUPPLY & INSTALLATION OF 900KVAR PFI	1	3,745,898	3,745,898				
	10,023,473							
Net Total (Excl GST)								

Eleven Million Nine Hundred Forty Nine Thousand Seven Hundred Twenty Seven Rupees

Service Charges

S.No.	Description	Qty	Rate (Rs)	Amount(Rs)
1	INSTALLATION OF BREAKER	1	70,000	70,000
2	PANEL MODIFICATION, REPLACEMENT OF BREAKER AND BUS BAR MODIFICATION IN EXISTING LT	1	180,000	180,000
	250,000			

Two Hundred Fifty Thousand Rupees only

CLIENT: AL KARAM TOWEL

PROJECT: M/S Supply of PANELS FOR AL KARAM TOWEL

COMPONENTS COSTING AS PER PROVIDED DETAILS

·	DESCRIPTION	RAT	ING	MAKE	QTY		
		AMP	SC				
	SUPPLY OF NEW 3200A BREAKER, COPPER MA NCOMING FROM K.E 1	IN BUS AND LINKS IN	EXISTING PANEL				
,	ACB TP (ADJ.)	3200A	100kA	ABB	1		
Ī	MOTOR MECHANISM 220V AC			ABB	1		
-	JVT			ABB	1		
,	SHUNT OPENING			ABB	1		
	SHUNT CLOSING			ABB	1		
(CTs	3200/5A		METLEX	3		
ħ	PHASE INDICATION LIGHTS (R/Y/B)			S.A./CAMSCO	3		
-	CONTROL MCB / FUSE + BASE	2A		CAMSCO / HIMEL	6		
-	BUSBAR PER PHASE + NEUTRAL	1X100 X 5	SERVICES	LOVATA	4		
-	BUSBAR EARTH	80 X 05	SERVICES	LOVATA	1		
Ľ	SUSBAIL EAINTT	80 X 05	SERVICES	LOVATA			
-	SUPPLY OF 3200A AUTO PHASE REVERSAL PANEL						
-	ACB TP(ADJ.)	3200A	100kA	ABB	2		
-	JVT	220VAC		ABB	2		
-	SHUNT OPENING	220VAC		ABB	2		
_	SHUNT CLOSING	220VAC		ABB	2		
Ľ	MOTOR MECHANISM	220VAC		ABB	2		
	CTs			FICO/METALEX	3		
Į	ENERGY ANALYZER	220VAC	R/Y/B	CIRCUTOR / EQU	1		
[PHASE INDICATION LIGHTS (R/Y/B)	2A		CAMSCO / HIMEL	3		
(CONTROL MCB / FUSE + BASE	3200/5A		CAMSCO / HIMEL	3		
	CONTROL SECTION:						
Ī	EVR RELAY			INTER/EQU.	1		
F	TIMER WITH BASE			AUTONICS/ EQU.	2		
-	NDICATION LIGHTS (NORMAL G)	220VAC		CAMSCO / HIMEL	1		
-	NDICATION LIGHTS (ABNORMAL R)	220VAC		CAMSCO / HIMEL	1		
-	CONTROL MCB / FUSE + BASE	2A		CAMSCO / HIMEL	2		
_	PHASE SEQUENCE RELAY	2/1		EMIREL/EQU.	1		
_	CONTROL RELAY WITH BASE			PHOENIX	1		
_	THERMOSTATE RELAY			IMPORTED	1		
-	EXHAUST FAN WITH FILTER			IMPORTED	2		
L		L					
	SUPPLY & INSTALLATION OF 900KVAR PFI ACB TP	1600A	100kA	OWNED PROVIDED	1		
-			TOUKA	OWNER PROVIDED	1		
-	CTs	3200/5A		METLEX	1		
L	12 STAGE PFI RELAY			OWNER PROVIDED	1		
_	3 X 50KVAR = 150 KVAR (3 VARIABLE STAGE)						
Ц	POWER FACTOR CAPACITOR @ 415VAC	50KVAR		OWNER PROVIDED	3		
L	MAGNETIC CONTACTOR TP @ AC-3	105A		OWNER PROVIDED	3		
Į	MCCB TP	100A	25kA	OWNER PROVIDED	3		
(3 X 25KVAR = 150 KVAR (3 VARIABLE STAGE)						
	POWER FACTOR CAPACITOR @ 415VAC	25KVAR		OWNER PROVIDED	5		
	POWER FACTOR CAPACITOR @ 415VAC	25KVAR		NOKIAN	1		
-	MAGNETIC CONTACTOR TP @ AC-3	50A		FUJI / EQU.	6		
L	MCCB TP	50A	25kA	TERASAKI	6		
(6x100KVAR=600KVAR (6 VARIABLE STAGE):						
Ţ	POWER FACTOR CAPACITOR @ 415VAC	50KVAR		NOKIAN	12		
	MAGNETIC CONTACTOR TP @ AC-3	105A		FUJI / EQU.	12		
	MCCB TP	100A	25kA	TERASAKI	12		
	MANUAL - OFF - AUTO SWITCH		G/R	CAMSCO	12		
_	ON/OFF PUSH BUTTON (G/R)			S.A./CAMSCO	24		
- 17	ON/OFF INDICATION LIGHT (G/R)	2A	2A/5	CAMSCO / HIMEL	24		
-	CONTROL MCB / FUSE + BASE	1		EMAS	3		
(
(THERMOSTATE RELAY EXHAUST FAN WITH FILTER			IMPORTED IMPORTED	3		